# www.DalaSheelar.com HITACH

KAOHSIUNG HITACHI **ELECTRONICS CO.,LTD** P.O. BOX 26-27 2,13TH EAST ST. K.E.P.Z. KAOHSIUNG TAIWAN R.O.C. TEL:(07) 8211101(10 LINE) FAX:(07) 821-5860

FOR MESSRS

DATE. Nov.20,2002

# CUSTOMER'S ACCEPTANCE SPECIFICATIONS

# SP10Q002-Z1 CONTENTS

No.	ITEM	SHEET No.	PAGE
1	COVER	7B64PS 2701-SP10Q002-Z1-2	1-1/1
2	RECORD OF REVISION	7B64PS 2702-SP10Q002-Z1-2	2-1/1
3	GENERAL SPECIFICATIONS	7B64PS 2703-SP10Q002-Z1-2	3-1/1
4	ABSOLUTE MAXIMUM RATINGS	7B64PS 2704-SP10Q002-Z1-2	4-1/1
5	ELECTRICAL CHARACTERISTICS	7B64PS 2705-SP10Q002-Z1-2	5-1/2~2/2
6	OPTICAL CHARACTERISTICS	7B64PS 2706-SP10Q002-Z1-2	6-1/2~2/2
7	BLOCK DIAGRAM	7B64PS 2707-SP10Q002-Z1-2	7-1/1
8	INTERFACE TIMING CHART	7B64PS 2708-SP10Q002-Z1-2	8-1/3~3/3
9	DIMENSIONAL OUTLINE	7B63PS 2709-SP10Q002-Z1-2	9-1/3
		7B64PS 2709-SP10Q002-Z1-2	9-2/3~3/3
10	APPEARANCE STANDARD	7B64PS 2710-SP10Q002-Z1-2	10-1/3~3/3
11	PRECAUTION IN DESIGN	7B64PS 2711-SP10Q002-Z1-2	11-1/4~4/4
12	DESIGNATION OF LOT MARK	7B64PS 2712-SP10Q002-Z1-2	12-1/1
13	PRECAUTION FOR USE	7B64PS 2713-SP10Q002-Z1-2	13-1/1

\* When product will be discontinued, customer will be informed by HITACHI with twelve months prior announcement.

JOOKAL TOP ACCEPTED BY;

KAOHSIUNG HITACHI	Sh 7B64PS 2701-SP10Q002-Z1-2	PAGE	1-1/1
ELECTRONICS CO.,LTD.	No.		

# RECORD OF REVISION

DATE	SHEET No.	SUMMARY
Nov.20,02		5.2 Electrical Characteristics of Backlight
	SP10Q002-Z1-2	
	Page 5-2/2	Frequency fL 30 70 85 kHz Ta=25℃
		Changed
		ITEM SYMBOL MIN. TYP. MAX. UNIT COMMENT
		Frequency fL 40 70 85 kHz Ta=25℃
	7B64PS- 2709	I/F function revise :
	SP10Q002-Z1-2	FRAME → FLM
	Page 9-3/3	LOAD → CL1 CP → CL2
		DISP OFF → DOFF
		·
		·

ELECTRONICS CO.,LTD. DATE Nov.20,'02 No. 7B64PS 2702-SP10Q002-Z1-2 PAGE 2-1/1	KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2702-SP10Q002-Z1-2 PAGE 2-1/1
---	-------------------	------	------------	-----	--------------------------------------

# 3. GENERAL SPECIFICATIONS

(1) Part Name SP10Q002-Z1

(2) Module Size 120.0(W)mm×80.0(H)mm×7.0(D)mm

(3) Effective Display Area 88.1 mm min. × 60.0 mm min.

(4) Dot Size 0.335(W)mm × 0.335(H)mm

(5) Dot Pitch 0.35(W)mm × 0.35(H)mm

(6) Number of Dots 240 (W) × 160 (H)dots

(7) Duty 1/160

(8) LCD Film type back/white (Negative type)

The upper polarizer is anti-glare type.

(Hardness: 3H)

The bottom polarizer is transmissive type.

(9) Viewing Direction 6 O'clock

(10) Backlight Cold cathode fluorescent lamp.

(11) Weight (80g)

# 4. ABSOLUTE MAXIMUM RATINGS

# 4.1 ELECTRICAL ABSOLUTE MAXIMUM RATINGS.

VSS=0V:STANDARD

ITEM	SYMBOL	MIN.	MAX.	UNIT	COMMENT
Power Supply for Logic	VDD-VSS	0	6.5	V	
Power Supply for LC Drive	VDD-VEE	0	27.5	V	
Input Voltage	Vi	-0.3	VDD+0.3	V	Note 1
Input Current	li	0	1	Α	
Static Electricity	_	-	100	V	Note 2

Note 1. DOFF, FLM, CL1, CL2, D0~D3.

Note 2. Make certain you are grounded when handling LCM.

# 4.2 ENVIRONMENTAL ABSOLUTE MAXIMUM RATINGS.

ITEM	OPERATING		STO	RAGE	COMMENT
	MIN.	MAX.	MIN.	MAX.	
Ambient Temperature	0℃	<b>40</b> ℃	-20℃	<b>60</b> ℃	Note 2,3
	Note 6				
HUMIDITY	Note 1		Note 1		Without Condensation
		2.45m/s <sup>2</sup>		11.76m/s <sup>2</sup>	
Vibration	-	(0.25G)	_	(1.2G)	Note 4
				Note 5	
		29.4m/s <sup>2</sup>		490.0m/s <sup>2</sup>	
Shock	-	(3 G)	-	(50 G)	XYZ Directions
					Note 5
Corrosive Gas	Not Acce	otable	Not Accep	table	

Note 1 Ta ≤ 40°C : 85%RH max.

Ta>40°C : Absolute humidity must be lower.

Than the humidity of 85% RH at 40℃.

Note 2 Ta at -20 $^{\circ}$ C < 48h, at 60 $^{\circ}$ C < 168h.

- Note 3 Background color changes slightly depending on ambient temperature. This phenomenon is reversible.
- Note 4 5Hz~100Hz (Except resonance frequency and X,Y,Z each direction within 1h)
- Note 5 The module should be operated normally after finish the test.
- Note 6 Higher starting voltage of CFL and higher LCD driving voltage are needed while operating at 0℃.

The life time of CFL will be reduced while operating at 0°C need to make sure of value of IL and characteristics of inverter.

Also the response time at 0°C will be slower.

KAOHSIUNG HITACHI		Nov 20 '02	Sh.	7B64PS 2704-SP10Q002-Z1-2 F		1 1/1
ELECTRONICS CO.,LTD.	DATE	Nov.20,'02	No.	/ B04F3	AGE	4-1/1

# 5. ELECTRICAL CHARACTERISTICS

# 5.1 ELECTRICAL CHARACTERISTICS

I TEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT
Power Supply Voltage	VDD-VSS	, <b>-</b>	4.75	5.0	5.25	V
For Logic			3.0	3.3	3.6	
Power Supply Voltage	VEE-VSS	-	-23.1	-22.0	-20.9	V
For Lc Driving				•		
Input Voltage	VI	H Level	0.8VDD		VDD	V
Note 1	VI	L Level	0	-	0.2VDD	V
Power Supply Current	IDD					
For Logic		Note 2	_	1.9	-	mA
Note 2						
Power Supply Current	IEE					
For LC Driving		Note 2	-	1.5	-	mA
Note 2						
Recommended LC		Ta= 0°C , <i>φ=</i> 0°	_	22.4	-	V
LC Driving Voltage	VDD-VEE	Ta=25℃, <i>φ=</i> 0°	-	20.5	-	V
Note 3		Ta=40°C , <i>φ</i> =0°	-	19.2	_	V
Frame Frequency	fFLM	_	70	75	140	Hz
Note 4	II LIVI	_	,,,	,,,	170	_ ' '

Note 1 DOFF, fFLM, CL1, CL2, D0~D3.

Note 2 fFLM =75Hz,Test pattern is all "Q". VDD-VEE=20.5V,Ta=25℃

Note 3 Recommended LC driving voltage fluctuate about ±1.0V by each module. Test pattern is all "Q"

Note 4 Need to make sure of flicking and rippling of display when setting the FLM frequency in your set.

KAOHSIUNG HITACHI		Nov.20,'02	Sh.	7B64PS 2705-SP10Q002-Z1-2 PAG	F	5_1/2
ELECTRONICS CO.,LTD.	DATE	1100.20, 02	No.	7B04F3 2703-3F 10Q002-21-2   AC	_	Q- 172.

# 5.2 ELECTRICAL CHARACTERISTICS OF BACKLIGHT

ITEM	SYMBOL	MIN.	TYP.	MAX.	UNIT	COMMENT
Lamp Voltage	VL	-	300	-	V	Ta=25°C
Frequency	fL	40	70	85	kHz	Ta=25°C
Lamp Current	IL	4	4.5	5	mA	Ta=25℃
Starting	VS	(1000)	-	-	V	Ta=25℃
Discharge Voltage	Note 2					

- Note 1: Please certainly inform HITACHI before designing lamp drive circuit according to the above specifications.
- Note 2: Staring discharge voltage is increased when LCM is operating at lower temperature.

  Please check the characteristics of inverter before appling to your set.
- Note 3: Average life time of CFL will be decreased when LCM is operating at lower temperature.
- Note 4: Under lower driving frequency of the inverter, a certain backlight (From CFL & CFL reflection sheet) may generate sound noise. Before designing the inverter, please consider drining frequency and check sound noise from the backlight system.
- Note 5 : CFL life time.

  MTBF=About 20K Hours at 25℃ IL=4.5mA

  Please note that MTBF is not a guaranteed value.

  This is a target value for LCM design.
- Note 6: Recommend inverter is INVC445(12V) and INVC473(5V).


# 6. OPTICAL CHARACTERISTICS

1 OPTICAL CHARACTERISTICS Ta=25°C(BACKLIGHT C										
ITEM		CONDITIONAL	MIN.	TYP.	MAX.	UNIT	NOTE			
Viewing Angle	<i>φ</i> 2- <i>φ</i> 1	K≧2.0	-	40	_	Deg.	1,2			
Contrast Ratio	K	φ=0°, θ=0°	-	20	-		3			
Response Time (Rise)	tr	φ=0°, θ=0°	_	160	<b>-</b>	ms	4			
Response Time (Fall)	tf	$\phi$ =0 $^{\circ}$ , $\theta$ =0 $^{\circ}$	_	110	-	ms	4			


(Measure Condition By HITACHI)

Note 3. Definition of contrast "K"


Note 1. Definition of  $\theta$  and  $\phi$ (Normal)




Brightness on selected dot (B1) Brightness on non-selected dot (B2)




Note 2. Definition of viewing angle  $\phi$ 1 and  $\phi$ 2:





Note 4. Definition of optical response



KAOHSIUNG HITACHI	  DATE	Nov.20,'02	Sh.	7B64PS 2706-SP10Q002-Z1-2 PAGE	6-1/2
ELECTRONICS CO.,LTD.		(101.20, 02	No.		

# 6.2 OPTICAL CHARACTERISTICS OF BACKLIGHT

(LCM, BACKLIGHT ON , Ta=25°C)


(4000)000000000000000000000000000000000						
ITEM	MIN.	TYP.	MAX.	UNIT	NOTE	
Brightness	80.0	120.0	_	cd/m²	IL=4.5mA	
					Note 1,2	
Rise Time	-	5	-	Minute	IL=4.5mA	
					Brightness 80%	
Brightness		-	±30	%	Under mentioned	
Uniformity					Note 1,3	


CFL : Initial, Ta=25℃, VDD-VEE=20.5V Display data should be all "ON".

Note 1. Measurement after 10 minutes of CFL operating.


Note 2. Brightness control: 100%


Note 3.Measurement of the following 9 places on the display. Definition of the brightness tolerance.





KAOHSIUNG HITACHI	DATE	Nov.20.'02	Sh.	7B64PS 2706-SP10Q002-Z1-2 PAGE	6-2/2
ELECTRONICS CO.,LTD.	DAIL	1404.20, 02	No.	100 to 0 2700 or 10 0002 21 2   1 AOE	0-212






# 8.2 TIMING CHARACTERISTICS


# 0°C ≤Ta ≤40°C, VDD=5V±5%

ITEM	SYMBOL	MIN.	TYP.	MAX.	UMIT
CL2 Frequency	fCP	-	-	6.5	MHz
CL2 Pulse Width	tw	63	-	-	ns
CL2 Rise, Fall Time	tr,tf	_	-	20	ns
Data Set Up Time	tDSU	50	_	ı	ns
Data Hold Time	tDHD	50	-	-	ns
CL1 Set Up Time	tLSU	80		-	ns
CL1 → CL2 Time	tLC	80		ī	ns
"FLM" Set Up Time	tSETUP	100	-	-	ns
"FLM" Hold Time	tHOLD	100	-	ľ	ns
"CL1" Pulse Width	tWC	125	-	-	ns




KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2708-SP10Q002-Z1-2	PAGE	8-2/3
ELECTRONICS CO.,LTD.	DATE	1404.20, 02	No.	750-1 0 2700 01 10 0002 21 2		

# 8.3 TIMING OF POWER SUPPLY AND INTERFACE SIGNAL



The missing pixels may occur when the lcm is driven except above power interface timing sequence.

# 8.4 POWER SUPPLY FOR LCM




C: 3.3µF(Aluminum electrolytic capacitor)


VR:10~20kΩ

Tr:2SA673APKC(hFE=100,IC=500mA)or equivalent Tr.

KAOHSIUNG HITACHI	האדר	Nov 20 202	Sh.	7B64PS 2708-SP10Q002-Z1-2 PAGE	0 2/2
ELECTRONICS CO.,LTD.	DATE		No.	7B04P3 2700-SP T0Q002-21-2 PAGE	0-3/3



# 9.2 DISPLAY PATTERN



# 9.3 INTERFACE PIN CONNECTION

I/F1: Molex/52103-1217

(Suitable FPC: 1.0 Pitch, Pin, 0.3t)

INTER	RFACE	PIN No.	SIGNAL	LEVEL	FUNCTION
		1	FLM	Н	First Line Marker
		2 CL1		H→L	Data Latch
		3	CL2	H→L	Data Shift
		4	4 VDD		Power Supply For Logic
	5	VSS	_	GND	
LCM	1014 1/54	6	VEE	_	Power Supply For LC
LCM	I/F1	7	D0		·
		8	D1	H/L	Display Data
		9	D2	'"L	Display Data
		10	D3		
	,	11	DOFF	H/L	H:ON / L:OFF
		12	GND	-	GND

INTER	FACE	PIN No.	SIGNAL	LEVEL	FUNCTION
		1	VCFL(+)		CFL Supply For CFL
CFL	2	N.C	-		
LCM	I/F2	3	N.C	_	
		4	VCFL(-)	-	CFL GND

CFL I/F2: Mltsumi/M63M83-04

Suitable Connector: Mitsumi M61M73-04

Mitsumi M60-04-30-1149(Straight) Mitsumi M60-04-30-1349(Angle)


KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2709-SP10Q002-Z1-2	PAGE	9-3/3
ELECTRONICS CO.,LTD.	DAIL	1404.20, 02	No.	, 20 H O Z, 00 O H O G O Z Z Z Z	.,	

# 10. APPEARANCE STANDARD


# 10.1 APPEARANCE INSPECTION CONDITION

Visual inspection should be done under the following condition.

- (1) In the dark room
- (2) With CFL panel lighted with prescribed inverter circuit.
- (3) With eyes 25cm distance from LCM.
- (4) Viewing angle within 45° from the vertical line to the center of LCD.



# 10.2 DEFINITION OF EACH ZONE



A Zone: effective viewing area (Refer to our drawing)

B Zone: except A zone

KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2710-SP10Q002-Z1-2	PAGE	10-1/3
ELECTRONICS CO.,LTD.	DAIL	1404.20, 02   1	No.			

# 10.3 APPEARANCE SPECIFICATION

\*) If the problem occurs about this item, the responsible person of both party (customer and HITACHI) will discuss more detail.


No.	ITEM		CRIT	ERIA	CRITERIA						
	Scratches	Distinguished o (To be judged		•		*	-				
	Dent	Same as above	9			*	_				
	Wrinkles in Polarizer	Same as above	9			*	_				
	Bubbles	Average D	iameter	Ma	ximum Number						
		D(mr			Acceptable						
			0.2		Ignore						
		0.2 <d≦< td=""><td></td><td></td><td colspan="2">12</td><td>  -  </td></d≦<>			12		-				
		0.3 <d≦< td=""><td><b>≨0.5</b></td><td></td><td>3</td><td></td><td></td></d≦<>	<b>≨0.5</b>		3						
		0.5 <d none<="" td=""><td></td></d>									
Ι.	Stains,		Filam	entous							
L	Foreign	LENGTH	WIDT		Maximum Number						
	Materials	L(mm)	W(mn		Acceptable						
	Dark Spot	L≦2.0	W≦0.03		Ignore						
C		L≦3.0	0.03 <w≦0.05< td=""><td>6</td><td>1 1</td><td></td></w≦0.05<>		6	1 1					
		-	0.05 <w< td=""><td></td><td>None</td><td></td><td></td></w<>		None						
				und							
		Average Dia-	Maximum N		Space	О	-				
l D		Meter D(mm)	Accepta								
		D<0.2	IGNOF	RE							
		0.2 ≦D<0.33	8		10mm	_					
		0.33≦D	None		-						
		The Whole	Filamentous	s + Roun	d = 10						
		Number									
		Those Wiped C				0	0				
	Color Tone	To Be Judge E		Limit Sa	ample	0	<u>-</u>				
	Color Uniformity	Same As Above				0	-				
	Pinhole	$(a + b)/2 \le 0.15 \text{m}$									
		0.15<(a + b)/2≤			ble≦10	О	-				
		C≦0.0	3 Ignore	!		L					

· •							
KAOHSIUNG HITACH	IDATE	Nov.20,'02	Sh.	7B64PS 2710-SP10Q002-Z1-2 F	PAGE	10-2/3	
ELECTRONICS CO.,L	TD.		No.		ļ		


No.	ITEM		CRITER	IA		Α	В
	Contrast Irregularity (Spot)	Average Diameter D(mm)	Contrast	Maximum Number Acceptable	Minimum Space		
		D≦0.25	То Ве	Ignore	-	0	-
	:	0.25 <d≦0.35< td=""><td>Judged By</td><td>≦10</td><td>20mm</td><td></td><td></td></d≦0.35<>	Judged By	≦10	20mm		
		0.35 <d≦0.5< td=""><td>HITACHI Limit</td><td><b>≦</b>4</td><td>20mm</td><td></td><td></td></d≦0.5<>	HITACHI Limit	<b>≦</b> 4	20mm		
1.		0.5 <d -<="" none="" sample="" td=""><td></td></d>					
C	Contrast Irregularity (Filamentous)	Width W(mm)	Length L(mm)	Maximum Number Acceptable	Minimum Space		
		W≦0.25	L≦1.2	≦2	20mm	o	
		W≦0.2	L≦1.5	≦3	20mm		-
		W≦0.15	L≦2.0	<b>≦</b> 3	20mm		
		W≦0.1	L≦3.0	<b>≦</b> 4	20mm		
		The Whole Nu	ımber	≤6	3		
	Rubbing Scratch	To Be Judged	By HITACHI St	andard		0	

# NOTE


(1) Definition of average diameter D



(2) Definition of length L and width W



(3) Definition of pinhole




KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2710-SP10Q002-Z1-2 PAGE	10 2/3
ELECTRONICS CO.,LTD.	DATE		No.	7604F3 27 10-3F 10Q002-21-2 FAGE	10-3/3

# 11. PRECAUTION IN DESIGN

# 11.1 Mounting Method

Since the module is so constructed as to be fixed by utilizing fitting holes in the printed circuit board as shown below, it is necessary to take consideration the following items on attachment to a frame.



- (1) Use of protective plate, made of an acrylic plate, etc. In order to protect a polarizer and LC cell.
- (2) To prevent the module cover from being pressed, The spacers between the module and the fitting plates should be longer than 0.5mm.
- (3) We recommend you to use protective spacer as figure for protecting LCD module from any kind of shock to your set.
- 11.2 LC driving voltage(VEE) and viewing angle range.

  Setting VEE out of the recommended condition will be a cause for a change of viewing angle range.

KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2711-SP10Q002-Z1-2	PAGE	11-1/4
ELECTRONICS CO.,LTD.	DATE	1400.20, 02	No.	75041 0 27 11 01 10 00 02 21 2		

# 11.3 CAUTION AGAINST STATIC CHARGE

As this module is provided with C-MOS LSIs, the care to take such a precaution as to grounding the operator's body is required when handling it.

### 11.4 POWER ON SEQUENCE

Input signals should not be applied to LCD module before power supply voltage is applied and reaches to specified voltage (5  $\pm$ 0.25V) if above sequence is not kept, C-MOS LSIs of LCD modules may be damaged due to latch up problem.

# 11.5 PACKAGING

- (1) No. leaving products is preferable in the place of high humidity for a long period of time. For their storage in the place where temperature is 35℃ or higher, special care to prevent them from high humidity is required. A combination of high temperature and high humidity may cause them polarization degradation as well as bubble generation and polarizer peel-OFF. Please keep the temperature and humidity within the specified range for use and storing.
- (2) Since upper polarizers and lower aluminum plates tend to be easily damaged, they should be handled with full care so as not to get them touched, pushed or rubbed by a piece of glass. Tweezers and anything else which are harder than a pencil lead 3H.
- (3) As the adhesives used for adhering upper/lower polarizes and aluminum plates are made of organic substances which will be deteriorated by a chemical reaction with such chemicals as acetone, toluene ethanol and isopropyl-alcohol. The following solvents are recommended for use:

### normal hexane

Please contact us when it is necessary for you to use chemicals other than the above.

(4) Lightly wipe to clean the dirty surface with absorbent cotton waste or other soft material like chamois, soaked in the chemicals recommended without scrubbing it hardly.

To prevent the display surface from damage and keep the appearance in good state, it is sufficient, in general, to wipe it with absorbent cotton.

KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2711-SP10Q002-Z1-2	PAGE	11-2/4
ELECTRONICS CO.,LTD.	DATE	1100.20, 02	No.	175041 6 27 11-01 10 0002 21 2	, ,,,,,,	11217

- (5) Immediately wipe off saliva off saliva or water drop attached on the display area because its long period adherence may cause deformation or faded color on the spot.
- (6) Fogy dew deposited on the surface and contact terminals due to coldness will be cause for polarizer damage, stain and dirt on product. When necessary to take out the products from some place at low temperature for test, etc. It is required them to be warmed up in a container once at the temperature higher than that of room.
- (7) Touching the display area and contact terminals with bare hands and contaminating them are prohibited, because the stain on the display area and poor insulation between terminals are often caused by being touched by bare hands.

(There are some cosmetics detrimental to polarizers.)

(8) In general the quality of glass is fragile so that it tends to be cracked or chipped in handling, specially on its periphery down, etc.

# 11.6 CAUTION FOR OPERATION

- (1) It is an indispensable condition to drive LCD's within the specified voltage limit since the higher voltage than the limit causes the shorter LCD life. An electrochemical reaction due to direct current causes LCD's undesirable deterioration, so that the use of direct current driver should be avoided.
- (2) Response time will be extremely delayed at lower temperature than the operating temperature range and on the other hand at higher temperature LCD's show dark blue color in hem.

However those phenomena do not mean malfunction or out of order with LCD's which will come back in the specified operating temperature range.

- (3) If the display area is pushed hard during operation, some font will be abnormally displayed but it resumes normal condition after turning off once.
- (4) A slight dew depositing on terminals is a cause for electrochemical reaction resulting in terminal open circuit.

Usage under the relative condition of 40°C 50%RH less is required.

KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2711-SP10Q002-Z1-2 PAGE	11_3//
ELECTRONICS CO.,LTD.	DATE		No.	7604F3 27 11-3F 10Q002-21-2 FAGE	:   1 1-3/ <del>4</del>

# 11.7 STORAGE

In case of storing for a long period time (For instance, years)

For the purpose of replacement use, the following ways are recommended.

- (1) Storage in a polyethylene bag with the opening sealed so as not to enter fresh air outside in it, and with no desiccant.
- (2) Placing in a dark place where neither exposure to direct sunlight nor light is keeping temperature in the range for  $0^{\circ}$  to  $35^{\circ}$ .
- (3) Storing with no touch on polarizer surface by anything else.

  (It is recommended to store them as they have been contained in the inner container at the time of delivery for us.)

# 11.8 SAFETY


- (1) It is recommendable to crash damaged or unnecessary LCD's into pieces and wash off liquid crystal by either of solvents such as acetone and ethanol, which should up later.
- (2) When any liquid leaked out of a damaged glass cell in contact with your hands, please wash it off well with soap and water.

KAOHSIUNG HITACHI	D 4 T C	Nov. 20 102	Sh.	7B64PS 2711-SP10Q002-Z1-2	DACE	11 1/1
ELECTRONICS CO.,LTD.	DATE	Nov.20,'02	No.	7864PS 2711-SP10Q002-Z1-2	PAGE	- <del>4/4</del>

# 12. DESIGNATION OF LOT MARK

Lot mark

Lot mark is consisted of 4 digit number.



YEAR	FIGURE IN
	LOT MARK
2002	2
2003	3
2004	4
2005	5
2006	6

Note 1. Some products have alphabet at the end or the first.

	FIGURE IN		FIGURE IN
MONTH	LOT MARK	MONTH	LOT MARK
Jan.	01	Jul.	07
Feb.	02	Aug.	08
Mar.	03	Sep.	09
Apr.	04	Oct.	10
May	05	Nov.	11
Jun.	06	Dec.	12

WEEK	FIGURE IN
(DAY IN	LOT MARK
CALENDAR	
01~07	1
08~14	2
15~21	3
22~28	4
29~31	5

Location of lot mark: On the back side of LCM

2114 T

KAOHSIUNG HITACHI	DATE	Nov.20,'02	Sh.	7B64PS 2712-SP10Q002-Z1-2	DAGE	12_1/1
ELECTRONICS CO.,LTD.	DATE	NOV.20, U2	No.	7B04F3 2712-3F10Q002-21-2	FAGE	12-1/1

# 13. PRECAUTIPON FOR USE

- (1) A limit sample should be provided by the both parties on an occasion when the both parties agreed its necessity. Judgment by a limit sample shall take effect after the limit sample has been established and confirmed by the both parties.
- (2) On the following occasion, the handling of the problem should be decided through discussion and agreement between responsible persons of the both parties.
  - (1) When a question is arisen in the specifications.
  - (2) When a new problem is arisen which is not specified in this specifications.
  - (3) When an inspection specifications change or operating condition change in customer is reported to HITACHI, and some problem is arisen in this specification due to the change.
  - (4) When a new problem is arisen at the customer's operating set for sample evaluation in the customer site.

The precaution that should be observed when handling LCM have been explained above. If any points are unclear or if you have any requests, please contact HITACHI.

KAOHSIUNG HITACHI	D . TE	N 00 100	Sh.	7DC4DC 0742 CD400002 74 2 D	.ACE	10 1/1
ELECTRONICS CO.,LTD.	DATE	Nov.20,'02	No.	7B64PS 2713-SP10Q002-Z1-2 P	AGE	13-1/1