REVISIONS																								
LTR						DES	SCR	TIO	4								DA	TE (Y	R-MO	-DA)	T	APP!	ROVE	D
				1.8								is.					Γ			(Majgrery		AL WOODS	i digina yan	27 <del>11 12 - 14</del>
																	•				•			
REV																								
SHEET				L																				
REV		-	+	_	_	<u> </u>	_	_		_		-	Ц		<u> </u>	L	L	_	L					
	Т	REV	1_	ļ	├	-	_	$\vdash$	_	-			Н		<u> </u>	_	L	<b> </b>		_	_	-	_	
REV STATUS OF SHEETS	}	SHEE	T	1	2	3	4	5	6	7	8		10	,,	<del> </del>	_				┝		<u> </u>	-	
PMIC N/A				PRE	PARE	D BY	,	استسيا	<u>.</u>	L	<u>.                                    </u>	Ϊ,	10)		L	L	L	نـــا	L	<u> </u>		L	<u> </u>	L
			$\dashv$				. <i>C</i>	,,-	in			4		DEF	ENSI	E ELI	ECTR	ONK N, OH	S S	UPPI	LY CE	NTE	R	
STANDA					CKE	BY O.A.	ع.	B	عه(	nO		L	47.00	001	00.12									
MILITA DRAW			İ		BOV			1	<b>2</b>		1	/ ۲	AMPL	IFI	RCUI ER,	n, I	LINE	AR, HIC	INS	rrui Icoi	MENT. N	ATIC	N	
THIS DRAWING			. 4			14	4		25	Z		+		_					<del></del>					
FOR USE BY ALL AND AGENC	DEF	ARTMEN	ıτs	UKA			P <b>ROV</b> JST						SIZE	Į			68			<u>50</u>	62	_0	778	000
DEPARTMENT	OF [	DEFENSE	•	REV	ISION	LEV	EL					╊							L'			-0		
AMSC N/A			[										S	HEE	T					1				

DESC FORM 193 SEP 87

 $\prod$ 

 $\circ$  U.S. Government printing office: 1987 — 748-129/60911 5962--E1128

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

1. SCOPE 1.1 Scope. This drawing describes device requirements for class B microcircuits in accordance of  $1.7-1.06~\rm M_\odot - ST2-303$ , "Provisions for the use of MIL-STD-883 in conjunction with compliant TE-JAN devices". 1.2 Part number. The complete part number shall be as shown in the following example: 5962-87780 Drawing number Device type Case outline Lead finish per (1.2.1)(1.2.2)MIL-M-38510 1.2.1 Device type. The device type shall identify the circuit function as follows: Perfee tyre Generic number Circuit function 1NA101 Instrumentation amplifier with gain sense 02 INA101 Instrumentation amplifier 1.2.2 Case outline. The case outlines shall be as designated in appendix C of MIL-M-38510, and as follows: Outline letter Case outline D-1, (14-lead, .785" x .310" x .200"), dual-in-line package A-2, (10-lead, .370" x .185") can package C 1.3 Absolute maximum ratings. +20 V dc -20 V dc Internal power dissipation  $(P_D)$  - - - - - - - - -600 mW ٧± Output short circuit duration - - - - - - - - - continuous to ground -65°C to +150°C +300°C Lead temperature (soldering, 10 seconds) - - - - -Thermal resistance, junction-to-case  $(\theta_{JC})$  - - - - Thermal resistance, junction-to-ambient  $(\theta_{JA})$ : See MIL-M-38510, appendix C Case C -----+125°C/W Case I - - - - - -+220°C/W 1.4 Recommended operating conditions. +11 V dc to +20 V dc -11 V dc to -20 V dc Ambient operating temperature range (TA) ------55°C to +125°C **STANDARDIZED** SIZE A MILITARY DRAWING 5962-87780 DEFENSE ELECTRONICS SUPPLY CENTER REVISION LEVEL SHEET DAYTON, OHIO 45444

DESC FORM 193A SEP 87

**★ U. S. GOVERNMENT PRINTING OFFICE: 1988—549-904** 

## 2. APPLICABLE DOCUMENTS

2.1 Government specification and standard. Unless otherwise specified, the following specification and standard, of the issue listed in that issue of the Department of Defense Index of Specifications and Standards specified in the solicitation, form a part of this drawing to the extent specified herein.

SPECIFICATION

**MILITARY** 

MIL-M-38510

- Microcircuits, General Specification for.

**STANDARD** 

**MILITARY** 

MIL-STD-883

Test Methods and Procedures for Microelectronics.

(Copies of the specification and standard required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

- 2.2 Order of precedence. In the event of a conflict between the text of this drawing and the references cited herein, the text of this drawing shall take precedence.
  - 3. REQUIREMENTS
- 3.1 Item requirements. The individual item requirements shall be in accordance with 1.2.1 of MIL-STD-883, "Provisions for the use of MIL-STD-883 in conjunction with compliant non-JAN devices" and as specified herein.
- 3.2 <u>Design, construction, and physical dimensions.</u> The design, construction, and physical dimensions shall be as specified in MIL-M-38510 and herein.
  - 3.2.1 <u>Terminal connections</u>. The terminal connections shall be as specified on figure 1.
  - 3.2.2 Block diagrams. The block diagrams shall be as specified on figure 2.
  - 3.2.3 Case outlines. The case outlines shall be in accordance with 1.2.2 herein.
- 3.3 Electrical performance characteristics. Unless otherwise specified, the electrical performance characteristics are as specified in table I and apply over the full ambient operating temperature range.
- 3.4 Marking. Marking shall be in accordance with MIL-STD-883 (see 3.1 herein). The part shall be marked with the part number listed in 1.2 herein. In addition, the manufacturer's part number may also be marked as listed in 6.4 herein.
- 3.5 Certificate of compliance. A certificate of compliance shall be required from a manufacturer in order to be listed as an approved source of supply in 6.4. The certificate of compliance submitted to DESC-ECS prior to listing as an approved source of supply shall state that the manufacturer's product meets the requirements of MIL-STD-883 (see 3.1 herein) and the requirements herein.

STANDARDIZED MILITARY DRAWING	SIZE A		5962-87780		
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL		SHEET 3	

. j. s. . .

DESC FORM 193A

± U. S. GOVERNMENT PRINTING OFFICE: 1988—549-904

TABLE I. Electrical performance characteristics. Conditions  $\frac{1}{-55}^{\circ}\text{C} \leq \text{T}_{\text{A}} \leq +125^{\circ}\text{C}$  unless otherwise specified Test Symbol Group A Limits Unit subgroups Min | Max Range of gain  $A_V = 1 + (40k/R_G) \frac{2}{}$ Αy 1, 2, 3 1000 **V/V** Gain equation error T<sub>A</sub> = +25°C EAV Ay = 1 0.05 % FS Ay = 10 0.10 Ay = 100 0.10 Ay = 1000 0.40 DC nonlinearity T<sub>A</sub> = +25°C 3/ Ay = 1 .005 Ay = 10 .005 Ay = 100 1.007 Ay = 1000.025 Gain temperature coefficient TCAV Ay = 1 5, 6 ppm/°C Ay = 10 25 Ay = 100 30 Ay = 1000 50 Output voltage V<sub>OP</sub>  $R_L = 2 k\Omega$ 4, 5, 6 **±10** ٧ Output current Io  $R_L = 2 k\Omega$ 4, 5, 6 ±5 mΑ See footnotes at end of table. **STANDARDIZED** SIZE Α 5962-87780 MILITARY DRAWING **DEFENSE ELECTRONICS SUPPLY CENTER REVISION LEVEL** SHEET DAYTON, OHIO 45444 DESC FORM 193A SEP 87

**★ U. S. GOVERNMENT PRINTING OFFICE: 1988—549-904** 

Powered by ICminer.com Electronic-Library Service CopyRight 2003

TABLE I. Electrical performance characteristics - Continued. Test |Symbol Conditions Conditions  $\frac{1}{-55^{\circ}\text{C}} < \text{T}_{\text{A}} < +125^{\circ}\text{C}$  unless otherwise specified |Group A Limits Unit Isubgroups Min | Max Input offset voltage 4/ TA = +25°C 1410 Ay = 101 ±75 μV Ay = 1000 ±50 Input offset voltage  $|\Delta V_{IO}/\Delta T|$   $T_A = +125^{\circ}C$ μV/°C Ay = 102 1+2.5 | temperature coefficient  $|A_V| = 1000$ l±1.751  $T_A = -55$ °C |Ay = 10|3 1 ± 2.5 Ay = 1000 I±1.75 Input offset voltage **IPSRR** V+ = +5 V μ**V/V** Ay = 10 1 ±35 | supply coefficient V = -5 V $|A_V| = 1000$ ±2 Ay = 10 2, 3 ±40 |Ay = 1000|±5 Initial input bias current IB 1, 2, 3 ±30 Initial input offset 110 1, 2, 3 ±30 nΑ current Input voltage linear response range VIN 1, 2, 3 | ±10 ٧ Input voltage common CMRR DC to 60 Hz Ay = 11, 2, 3 | 80 ďΒ mode rejection 5/ Ay = 10 96 Ay = 100 to 1000 106 Power supply rated ۱۷± 1, 2, 3 | ±5 ±20 | voltage See footnotes at end of table. **STANDARDIZED** SIZE Α **MILITARY DRAWING** 5962-87780 DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444 **REVISION LEVEL** SHEET

DESC FORM 193A SEP 87

★ U. S. GOVERNMENT PRINTING OFFICE: 1988--550-547

Test	Symbol	Conditio	ns <u>1</u> /	Group A	Limits		Unit
		-55°C < TA <   unless otherwis	subgroups      	Min	     Max		
Power supply quiescent current	IQ	 		1, 2, 3		  ±8.5	   mA 
Dynamic response slew rate	SR	$R_1 = 2 k\Omega$	Ay = 1 to	4	0.2	<u> </u>	1 1 <b>V</b> /μ
	 	 	100 	5, 6	0.1	 	
Dynamic response settling settling time	ts	±10 V to 0.01%   of final value.	Ay = 1	9, 10, 11	30		μS
	!		Av = 100	1 1	50	!	!

- $\underline{1}/$  V+ = +15 V, V- = -15V, R<sub>L</sub> = 2 k $\Omega$ , unless otherwise specified.
- $\underline{2}/$  Typically, the tolerance of RG will be the major source of gain error.
- 3/ -Input = 0 V, +input is varied to enable nonlinearity error to be measured between -10 V < output < +10 V and determining worst case deviation from straight line connecting these end points at each gain setting.
- 4/ Adjustable to zero at any one gain.
- 5/ 1 k $\Omega$  source imbalance applies only to  $T_A$  = +25°C.
- 3.6 Certificate of conformance. A certificate of conformance as required in MIL-STD-883 (see 3.1 herein) shall be provided with each lot of microcircuits delivered to this drawing.
- 3.7 Notification of change. Notification of change to DESC-ECS shall be required in accordance with MIL-STD-883 (see 3.1 herein).
- 3.8 Verification and review. DESC, DESC's agent, and the acquiring activity retain the option to review the manufacturer's facility and applicable required documentation. Offshore documentation shall be made available onshore at the option of the reviewer.


STANDARDIZED MILITARY DRAWING	SIZE A		5962-87780	0
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444	-	REVISION LEVEL	SHEET	6

DESC FORM 193A SEP 87

± U. S. GOVERNMENT PRINTING OFFICE: 1988--550-547

Device types 01 02 Case outlines C I Terminal Terminal symbols number OUTPUT GAIN SET 1 2 OFFSET ADJ OFFSET ADJ GAIN SET 2 3 -INPUT GAIN SENSE 1 GAIN SET 1 5 +INPUT OFFSET ADJ OFFSET ADJ A1 OUTPUT 6 7 COMMON OUTPUT 8 A2 OUTPUT 10 11 GAIN SET 2 GAIN SENSE 2 -INPUT 12 13 +INPUT ------14 COMMON FIGURE 1. Terminal connections. **STANDARDIZED** SIZE 5962-87780 A **MILITARY DRAWING** DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444 **REVISION LEVEL** SHEET DESC FORM 193A SEP 87

± U. S. GOVERNMENT PRINTING OFFICE: 1988--549-904



Powered by ICminer.com Electronic-Library Service CopyRight 2003

- 4. QUALITY ASSURANCE PROVISIONS
- 4.1 Sampling and inspection. Sampling and inspection procedures shall be in accordance with section  $\overline{4}$  of MIL-M-38510 to the extent specified in MIL-STD-883 (see 3.1 herein).
- 4.2 Screening. Screening shall be in accordance with method 5004 of MIL-STD-883, and shall be conducted on all devices prior to quality conformance inspection. The following additional criteria shall apply:
  - a. Burn-in test, method 1015 of MIL-STD-883.
    - Test condition A, B, C, or D using the circuit submitted with the certificate of compliance (see 3.5 herein).
    - (2)  $T_A = +125$ °C, minimum.
  - b. Interim and final electrical test parameters shall be as specified in table II herein, except interim electrical parameter tests prior to burn-in are optional at the discretion of the manufacturer.
- 4.3 Quality conformance inspection. Quality conformance inspection shall be in accordance with method 5005 of MIL-STD-883 including groups A, B, C, and D inspections. The following additional criteria shall apply.
  - 4.3.1 Group A inspection.
    - a. Tests shall be as specified in table II herein.
    - b. Subgroups 7 and 8 in table I, method 5005 of MIL-STD-883 shall be omitted.
  - 4.3.2 Groups C and D inspections.
    - a. End-point electrical parameters shall be as specified in table II herein.
    - b. Steady-state life test conditions; method 1005 of MIL-STD-883:
      - Test condition A, B, C, or D using the circuit submitted with the certificate of compliance (see 3.5 herein).
      - (2)  $T_A = +125^{\circ}C$ , minimum.
      - (3) Test duration: 1,000 hours, except as permitted by method 1005 of MIL-STD-883.

STANDARDIZED MILITARY DRAWING	SIZE A		59	962-87780	
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	,	SHEET 9	

DESC FORM 193A SEP 87

± U. S. GOVERNMENT PRINTING OFFICE: 1988-549-904

## TABLE II. Electrical test requirements.

MIL-STD-883 test requirements	Subgroups   (per method   5005, table I)
Interim electrical parameters (method 5004)	1
Final electrical test parameters (method 5004)	1*, 2, 3, 4
Group A test requirements (method 5005)	1 1, 2, 3, 4, 1 5, 6, 9, 10**, 1 11**
Groups C and D end-point electrical parameters (method 5005)	1

\* PDA applies to subgroup 1.\*\* Subgroups 10 and 11 shall be guaranteed if not tested.

## 5. PACKAGING

5.1 Packaging requirements. The requirements for packaging shall be in accordance with MIL-M-38510.

## 6. NOTES

- 6.1 <u>Intended use</u>. Microcircuits conforming to this drawing are intended for use when military specifications do not exist and qualified military devices that will perform the required function are not available for OEM application. When a military specification exists and the product covered by this drawing has been qualified for listing on QPL-38510, the device specified herein will be inactivated and will not be used for new design. The QPL-38510 product shall be the preferred item for all applications.
- 6.2 Replaceability. Microcircuits covered by this drawing will replace the same generic device covered by a contractor-prepared specification or drawing.
- 6.3 Comments. Comments on this drawing should be directed to DESC-ECS, Dayton, Ohio 45444, or telephone 513-296-5375.

**STANDARDIZED** SIZE A 5962-87780 **MILITARY DRAWING DEFENSE ELECTRONICS SUPPLY CENTER** REVISION LEVEL SHEET DAYTON, OHIO 45444 10

DESC FORM 193A SEP 87

**★ U. S. GOVERNMENT PRINTING OFFICE: 1988—549-904** 

6.4 Approved source of supply. An approved source of supply is listed herein. Additional sources will be added as they become available. The vendor listed herein has agreed to this drawing and a certificate of compliance (see 3.5 herein) has been submitted to DESC-ECS.

Military drawing part number	Yendor   CAGE   number	Vendor   similar part   number <u>1</u> /	Replacement military specification part number
5962-8778001CX	13919	INA101VG/883B	
5962-8778002IX	13919	INA101VM/883B	

 $\frac{1}{\text{to this}}$  . Do not use this number for item acquisition. Items acquired to this number may not satisfy the performance requirements of this drawing.

Vendor CAGE number

13919

Vendor name and address

Burr-Brown Corporation P.O. Box 11400 Tucson, AZ 85734

STANDARDIZED

MILITARY DRAWING

DEFENSE ELECTRONICS SUPPLY CENTER

DAYTON, OHIO 45444

SIZE A

5962-87780

REVISION LEVEL

SHEET 11

DESC FORM 193A SEP 87

**★ U. S. GOVERNMENT PRINTING OFFICE: 1988—549-904**